

E-mail: isdltvm@gmail.com,

Website: www.ijdl.org



Phone [Office] 2704953

[Library] 2704951

[Publication Unit] 2704282

INTERNATIONAL SCHOOL OF DRAVIDIAN LINGUISTICS

(Reg. No. 110/1977)

V.I.Subramoniam Memorial ISDL Complex, St.Xavier's College P.O.
Thiruvananthapuram-695 586, Kerala, INDIA

Prof. G.K. Panikkar, M.A. Ph.D.

Hon. Director

(Mob: 9387828502)

ISDL/ RW/2023-24/09

12.12.2023

NOTICE

The Notice No.ISDL/ RW/2023-24/08 dtd. 25.11.2023 is extended to
16.12.2023, 3pm

Prof. G.K.Panikkar
Hon. Director, ISDL.



E-mail: isdltvm@gmail.com,
Website: www.ijdl.org

Phone [Office] 2704953
[Library] 2704951
[Publication Unit] 2704282

INTERNATIONAL SCHOOL OF DRAVIDIAN LINGUISTICS

(Reg. No. 110/1977)

V.I.Subramoniam Memorial ISDL Complex, St.Xavier's College P.O.
Thiruvananthapuram-695 586. Kerala. INDIA

Prof. G.K. Panikkar, M.A. Ph.D.
Hon. Director.
(Mob: 9387828502)

ISDL/ RW/2023-24/08

25.11.2023

ദർശനം

മേനംകുളത്തു പ്രവർത്തിക്കുന്ന ഇന്റർനാഷണൽ സ്കൂൾ ഓഫ് ദ്രവീഡിയൻ ലിംഗ്വിസ്റ്റിക്സിന്റെ വിവിധ കെട്ടിടങ്ങളിൽ താഴെപ്പറയുന്ന റൂഫിംഗ് വർക്ക് ചെയ്യുന്നതിലേക്ക് പ്രവർത്തിപരിചയമുള്ളവരിൽ നിന്നും മത്സരാധിഷ്ഠിതമായ കൊട്ടേഷനുകൾ മുദ്രവച്ച കവറിൽ ക്ഷണിക്കുന്നു. കൊട്ടേഷനുകൾ സമർപ്പിക്കേണ്ട അവസാന തീയതി 2023 ഡിസംബർ 11-ാം തീയതി 3 മണി.

1. അഡ്മിനിസ്ട്രേറ്റീവ് ബ്ലോക്കിന്റെ മുകൾ ഭാഗത്ത് അലൂമിനിയം ഷീറ്റ് പാകി പണി പൂർത്തിയാക്കുന്നതിന്.
2. ആഡിറ്റോറിയത്തിന്റെ മുകൾഭാഗത്ത് അലൂമിനിയം റൂഫിംഗ് നിർമ്മിക്കുന്നതിന്.
3. ട്രൈബൽ ബ്ലോക്കിന്റെ സൺഷേഡ് ഷീറ്റ് റൂഫിംഗ് നിർമ്മിക്കുന്നതിന്.

കൂടുതൽ വിവരങ്ങൾക്ക് I.S.D.L. ഓഫീസുമായി ബന്ധപ്പെടുക. കൊട്ടേഷനുകൾ സ്വീകരിക്കുന്നതും വർക്ക് അലോട്ട് ചെയ്യുന്നതും സംബന്ധിച്ച അന്തിമതീരുമാനം I.S.D.L. ഡയറക്ടറിൽ നിക്ഷിപ്തമാണ്. Tel. No. 0471-2704953, website : www.ijdl.org

പ്രൊഫ. ജി.കെ. പണിക്കർ
ഹോണററി ഡയറക്ടർ, I.S.D.L.

**FABRICATION WORK FOR THE SEMIPERMANENT ROOFING TO THE FIRST FLOOR OF EXISTING
ADMINISTRATIVE BLOCK OF ISDL, MENAMKULAM, TRIVANDRUM**

Sl. No.	Quantity	Description	Rate/ m ²	Amount	
				Rs.	In Words
1	305 m ²	Roofing with 0.46mm Aluminium Roofing Sheet (Oralium/Indalco) over the Existing Frame Work, including providing 25x25x1.6 mm (TATA make) intermediate purlin to strengthen the existing frames, also providing extra eve projection up to 80 cm in horizontal with same section already done, primer with epoxy primer and two coats enamel paint to the whole body, necessary down water gutter using existing gutters etc complete. (area must be measured in horizontally- 305m ²)			

FABRICATION WORK FOR FIXING SEMIPERMANENT ROOFING TO THE FIRST FLOOR ROOF NEW LIBRARY AND AUDITORIUM BLOCK OF ISDL, MENAMKULAM, TRIVANDRUM

Sl. No.	Quantity	Description	Rate/ m ²	Amount	
				Rs.	In Words
1	340 m2	Roof Protection work with point 0.46mm Aluminium Roofing sheet (Indalco/Oralium) over 50x25x1.6mm (TATA make) GI Tube and 20x25x1.6mm TATA make Square Tube purlin directly to fix on the existing roof including 80 cm eve projection (area must be measured as actual surface) without rain water gutter etc complete including epoxy primer and two coats of enamel paint.			

**FABRICATION WORK FOR FIXING ALUMINIUM SUNSHADE AT THE TRIBAL BLOCK IN ISDL,
MENAMKULAM, TRIVANDRUM**

Sl. No.	Quantity	Description	Rate/ m ²	Amount	
				Rs.	In Words
1	22 m2	Providing sunshade protection work using 40x40x1.6mm Square Tube of TATA make as rafters and 25x25x1.6mm Square Tube TATA make as purlin and covered with 0.46mm Oraliun Aluminium Sheet including cutting, bending, welding and fixing to the existing wall with 100x100x6/4 mm base plate etc and painting, priming coat and enamel paint two coats etc complete.			